Statement showing the approximate quantities of work for constructing combined Office and Stores at Tumkur Town :—

Sl. No.	Items of work	Unit	Quantity
1	Earthwork excavation and filling in basement including a lead of 50 feet.	C.yd.	46
2	Levelling site and facilitating drainage	L. S.	
3	Stone jelly in lime mortar, concrete foundation ...	C.ft.	479
4	Masonry stone in lime mortar, foundation and basement ...	"	819
5	Burnt brick in clay, superstructure	"	3,093
6	Stone slabs 6" thick undressed	S.ft.	84
7	Stone slabs 6" thick roughly dressed for pillars including cutting slots for bressemmers.	"	66
8	Chunam plastering 2 coats	Sqr.	45·23
9	Chunam pointing with thread lines	"	1·65
10	White and colour washing 2 coats	"	46·88
11	Flooring with Cuddapah slabs 1½" thick on 3" stone jelly in lime concrete and cement pointed.	"	13·77
12	Roofing with corrugated galvanized iron sheeting 24 B. W. G. with galvanized iron screws and washers, sheets to overlap 12" at ends and 2 corrugations at sides.	"	21·84
13	Galvanized iron ridge sheeting 2 feet wide 22 B. W. G. with galvanized iron screws and washers.	R.ft.	52
14	Honney wood door panelled 2" thick shutter frames 6" x 4½" with bolts, hinges, etc., complete including tarring to frames as per drawing No. C-108.	S.ft.	48
15	Do do 1½" thick shutter frames 5" x 4" with bolts, hinges, etc., complete, including tarring to frames as per drawing No. C-108.	"	64
16	Honney wood windows glazed 1¼" thick shutter frames 4½" x 4" with iron bars 5/8" dia. with bolts hinges, etc., complete, including tarring to frames as per drawing No. C.-108.	"	105
17	Honney wood windows pannelled 1¼" thick shutter 4½" x 4" frames with iron bars 5/8" dia. with bolts, hinges, etc., complete, with a pigeon hole at bottom and plank at the sill including tarring to frames.	"	18
18	Honney wood ventilators glazed with iron bars including tarring to frames as per Drawing No. C.-108.	"	24
19	Painting with 2 coats of chocolate paint	Sqr.	16·21
20	Wrought iron work fixed complete	Cwt.	61·86

S. G. FORBES,
Chief Electrical Engineer
to the Government of Mysore.

SHIMOGA DIVISION:

Notice dated 24th August 1927.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 15th September 1927, for constructing Local Fund Dispensary, at Anavatti, Sorab Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M., and 5 P.M., on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 500 (five hundred only) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Constructing Local Fund Dispensary at Anavatti," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer Shimoga Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for "Constructing Dispensary and In-patient ward at Anavatti, Sorab Taluk."

No.	Items of work	Per	Quantity
1	Clearing site and levelling ground	Lump	sum
2	Earthwork excavation for foundation and filling in basement	C.yd.	118
3	Size (burnt) stone in chunam, foundation and basement	C.ft.	3,251
4	Burnt brick in chunam, superstructure	,,	5,441
5	Do arch work	,,	56
6	Burnt stone slabs dressed	S.ft.	602
7	Chunam plastering	Sqr.	96·76
8	Flooring with 9" Mangalore tiles, First Class on 3" concrete bed and cement pointing.	,,	8·11
9	Teakwood doors pannelled with double shutters including bolts, hooks, hinges, etc., complete.	S.ft.	250
10	Teakwood battened doors with double shutters including bolts, hooks, hinges, etc., complete.	,,	36
11	Teakwood pannelled windows with iron bars, glazed shutters inside, pannelled outside, including hinges, bolts, hooks, etc., complete.	,,	220
12	White and colour washing	Sqr.	96·76
13	Teakwood ventilators, glazed	S.ft.	90
14	Silicate painting to doors and windows	Sqr.	20·00
15	Teakwood work wrought and put up complete	C.ft.	157·00
16	Roofing with First Class Mangalore tiles on teak reepers, etc., complete.	Sqr.	31·37
17	Ridge and hip tiles with cement pointing	R.ft.	119
18	Teakwood eave-boards ornamental	,,	441
19	Teakwood pillars with base and capital	No.	13
20	Wood oiling to wood work	Sqr.	10·00
21	Tarring to wood work	,,	6·00
22	Zinc sheets to valleys	S.ft.	90
23	Teakwood planks ½" thick for valleys	,,	90
24	Teakwood finials	No.	4
25	Flooring with Kadapa slabs over 3" concrete bed and cement pointing.	Sqr.	9·10
26	Teakwood Gothic windows, treble, with glazed shutters, etc.	S.ft.	85
27	Ventilating tiles including cement pointing	No.	8
28	Concrete foundation	C.ft.	1,046

M. A. SREENIVASACHARI,
Executive Engineer.

CHITALDRUG DIVISION.

Notice dated 28th August 1927.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 1st October 1927, for the Construction of a Local Fund Dispensary Building at Bharmasagara in Chitaldrug Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug, between the hours of 11 A.M. and 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.—

Description of work	Unit of work	Rate per unit
	Vide Abstract enclosed.	

4. Each tender must be accompanied by a deposit of rupees 300 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for the Construction of a Local Fund Dispensary Building at Bharamasagara in Chitaldrug Taluk.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of quantities for Constructing Local Fund Dispensary Building at Bharamasagara, Chitaldrug District.

Sl. No.	Items of work	Per	Total quantity
1	Earthwork Excavating foundation and filling in basement ...	C.yd.	189
2	Filling foundation with concrete (stone jelly and mortar) ...	C.ft.	1,863
3	Burnt stone in mortar	,,	3,444
4	Burnt brick in mortar	,,	4,665
5	Stone slabs 6" thick dressed	S.ft.	435
6	Plastering with mortar	Sqr.	90·50
7	White and colour washing	,,	90·50
8	Pointing with cement mortar	,,	5·51
9	Arch work Brick in mortar	C.ft.	49
10	Teakwood work wrought and put up with wood oiling ...	,,	185·44
11	Teakwood pannel doors 1¼" thick shutters including bolts hinges, brass locks clamps etc., fittings complete ...	S.ft.	264
12	Teakwood battened doors 1¼" thick shutters including bolts hinges, brass locks clamps, etc., fittings complete ...	,,	16
13	Teakwood windows 1¼" thick, single side shutters ½ pannelled and half glazed in four halves with ¾" iron bars hinges clamps, bolts etc., complete	,,	247
14	Teakwood windows pannelled 1¼" thick with iron bars ¾" dia. including hinges, clamps etc., complete ...	,,	5
15	Teakwood windows battened 1¼" thick shutters with ¾" thick iron bars hinges, clamps etc., complete ...	,,	18
16	Teakwood wall shelves with pannelled shutters hinges hooks locks etc., complete with cross planks fittings ...	,,	95
17	Teakwood ventilators with glazed shutters, hooks, hinges ¾" iron bars and clamps etc., complete	,,	48
18	Teakwood Circular ventilators in gables glazed complete ...	,,	21
19	Teakwood planking for valleys	,,	257
20	Teakwood Eave board with painting	R.ft.	303
21	Teakwood pendents with painting	Each	13
22	Teakwood Finials do	,,	3
23	Seven inches square stone pillars with base and caps including champering at edges	,,	6
24	Roofing with 1st Class Mangalore tiles on teakwood reepers nails wood oiling to reepers, etc., complete... ...	Sqr.	32·73
25	Ridge tiles set in mortar	R.ft.	185

No.	Items of work	Per	Total Quantity
26	Flooring with 1½" to 2" thick Cudapah slabs on 3" concrete bed and cement pointing	Sqr.	6·90
27	Flooring with 1½" to 2" thick Cudapah slabs on sand bed and cement pointing	,,	·63
28	Flooring with 1st Class Mangalore tiles on 3" concrete and cement pointing	,,	10·00
29	Chacolate painting 2 coats	,,	6·86
30	Wood oiling 2 coats	,,	6·67
31	Plain Zinc sheets for valleys 3' wide	S.ft.	257
32	Binding walls to gable ends 1 foot inside 9" thick with brick in chunam and smooth plastering	R.ft.	66
33	Binding walls at top of gable roof ends	,,	38
34	Providing ventilating tiles	Each	4
35	Coping with brick in chunam	R.ft.	39
36	Providing date stone	Each	1
37	Do inscription (name board)	,,	1
38	Tarring wood work	Ls.	Ls.
39	Sinks in compounding room, etc.	Each	4
40	Drainage work	Ls.	Ls.
41	Levelling the site for the Dispensary	,,	,,
42	Clearing site and tarring to Latrine	,,	,,
43	Constructing Cistern and providing with buckets and C. I. outlet pipe	,,	,,
44	Clearing site and building over Chimney etc., complete for the kitchen	,,	,,
45	Unforeseen charges such as constructing walls at gables at ends ornamental work all round windows etc., rounding corners partition wooden complete	,,	,,
46	Honey comb work	Sqr.	2·00
47	Providing stone table with polished slab and uprights as per design complete	Each	1

A. TANDONI RAO,
Executive Engineer.

MEDICAL DEPARTMENT.

MINTO OPHTHALMIC HOSPITAL, BANGALORE.

Tender Notice.

Notice is hereby given that sealed tenders, in duplicate, on half sheet foolscap sized paper, will be received at the Office of the Superintendent, Minto Ophthalmic Hospital, Bangalore, by the undersigned at 11 A.M., on Thursday the 22nd September 1927, for the supply of articles of bedding and clothing (as per list annexed) required for the Minto Ophthalmic Hospital, for the year 1927-28.

2. No tender will be received after the date and hour abovementioned.

3. Tender to be superscribed "Tender for the supply of bedding and clothing" to the Minto Ophthalmic Hospital.

4. No tender will be received unless accompanied by a deposit of Rs. 50 in cash, or currency notes or Treasury receipts.

5. Tenders will be opened by the Superintendent, at his office on the date and at the hour abovementioned in the presence of such tenderers as may choose to attend.

6. The rate for each item must be specified in figures as well as in words, in ink and they must be for the particular kind or brand of the article as specified in the list appended hereto. The value of each tender must be worked out according to the rates tendered and the total value must also be entered in words. Tender not conforming to this rule will be rejected.

7. The quantities stated in the list are not guaranteed.

8. The Senior Surgeon does not bind himself to accept the lowest or any tender or to assign any reason for not accepting any tender.

9. The deposit of the successful tenderer will be retained, and will be forfeited to Government, if he fails to complete the contract.

10. No advance of cash will be made to the contractor; payments for the articles supplied in each month will be made, as soon as possible after the 10th of the following month on his producing the necessary bill with vouchers.

11. All articles, except when mentioned otherwise, should be of the first sort, any articles rejected on account of inferiority should be promptly replaced by articles of the required quality or will be purchased by the hospital authorities from outside and the charges debited to the contractor.